

## Notice Inviting Tenders for

**“Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms.**

**Tender No. 07/2018-2019/Engg. (C)**

### SCHEDULE OF BIDS

1	Tender document download / sale period	17.08.2018 to 30.08.2018
2	Last Date & time of submission of Tenders	31.08.2018 at 3:00 P.M.
3.	Pre-Bid Meeting	24.08.2018 at 3:00 P.M.
3	Date & time of Opening of Technical Bids	31.08.2018 at 4:00 P.M.
4	Opening of Price Bids	To be intimated separately only to technically eligible bidders.
5	Tender Fee	i) Rs. 560/- ( <i>Five hundred sixty</i> ) including Goods & Service Tax, if tender document purchased from National Institute of Biologicals, Noida. ii) No tender fee if downloaded by bidder at their own end.

Name of bidder	
Address of Bidder	
Phone Nos.	i- Landline Nos. ii- Cell Nos.
E-mail Id	
Contract Persons & their mobile nos.	i- ii- iii-

**August - 2018**



**NATIONAL INSTITUTE OF BIOLOGICALS**

*(Ministry of Health & Family Welfare)*

**A-32, SECTOR- 62 (INSTITUTIONAL AREA),**

**NOIDA - 201 309 (U.P)**

**Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014**

**e-mail: [info@nib.gov.in](mailto:info@nib.gov.in)**

**Website: [www.nib.gov.in](http://www.nib.gov.in)**



## NATIONAL INSTITUTE OF BIOLOGICALS

**Plot No.A-32, Sector-62(Institutional Area), NOIDA-201 309(U.P)**

Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014

E-mail: [info@nib.gov.in](mailto:info@nib.gov.in)

Website: [www.nib.gov.in](http://www.nib.gov.in)

### NOTICE INVITING TENDERS

#### Tender No. 07/2018-2019/Engg. (C)

Invitation to tenders for “Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms”.

Sealed tenders are invited from experienced work contractors, for “Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130 A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms”. Bidders are advised to quote competitive rates for this work, on the Price-Bid format given in the tender including T & P etc. required for proper completion of the work. The tender document can be down loaded from NIB Website [www.nib.gov.in](http://www.nib.gov.in) or Central Procurement Portal (CPP) Govt. of India from 17.08.2018 to 30.08.2018 or the same can be purchased from Finance Section of National Institute of Biologicals from 17.08.2018 to 30.08.2018 on all working days between 10:00 AM to 5:00 PM on payment of **Rs. 560/-** (*Five hundred sixty only*) towards tender fee only in the shape of demand draft in favour of “National Institute of Biologicals, Noida” payable at Noida.

Sealed tender should be dropped in tender box at NIB Noida, on or before the closing date, i.e., **31.08.2018** up to **3:00 P. M.** Technical bid shall be opened on the same day at **4:00 P. M.** in presence of the representatives of the bidders, who are present during opening of the tenders. Late tenders will not be received and treated as rejected.

Prospective bidders are advised to regularly scan through NIB website tender portal [www.nib.gov.in](http://www.nib.gov.in) as corrigendum/ amendments etc., if any, will be notified on this portal only and no separate intimation/ advertisement will be made in this regard.

(Dr. Shikha Yadav)  
Head Engineering Division i/c  
(For on behalf of Director, NIB, Noida)



## NATIONAL INSTITUTE OF BIOLOGICALS

**Plot No.A-32, Sector - 62 (Institutional Area), NOIDA - 201 309 (U.P)**

Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014

E-mail: [info@nib.gov.in](mailto:info@nib.gov.in)

Website: [www.nib.gov.in](http://www.nib.gov.in)

### **Tender No. 07/2018-2019/Engg. (C)**

**Invitation to tenders for “Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms”.**

#### **Introduction:**

National Institute of Biologicals (NIB), is an autonomous institution under the Ministry of Health & Family Welfare, Government of India, established on 27<sup>th</sup> January, 1992 and is to be the Central Drugs Laboratory for quality control of all indigenously produced and imported biological products. Presently, eight laboratories of the Institute are notified as Central Drugs Laboratory under provision of Drugs & Cosmetics Act and Rules. Institute plays a vital role in collaboration with CDSCO to strengthen the regulation of biologicals in India by averting the Not of Standard Quality Biologicals reaching the consumer, thereby promoting and protecting public health.

#### **1. Scope of Work:**

The works are to be carried out in a working Laboratory. The agency will execute the work in such a way so that there is minimum movement of manpower/material during working hours. Work plan will be discussed and coordinated with NIB.

PVC False Ceiling is to be fixed in a Store Room supported on frame made of steel tube of size 25mmx25mm. A Upvc hollow section of size 250mmx10mmx1mm ± 0.3mm average wall thickness will be fixed to the frame in such a way to conceal the tubular frame, with the help of self-tapping steel screws placed at interval of 600mm. Epoxy flooring is to be laid on the existing floor in Room No. L-0015. Coving (rounding) is to be provided along with all sides of the room. A gypsum board partition having 75mm overall thickness using 12.5 mm thick double skin tapered edged plain Gypsum board is to be installed to cover a machine back protruding from the wall. Gypsum board partition shall be painted with epoxy paint.

Miscellaneous works such as fixing Stainless Steel (SS) sink in the existing counter and providing & fixing glass spill barrier with sink as mentioned in BOQ are to be carried out. For drainage, PPR Pipe shall be laid by chasing the concrete floor and making hole in gypsum wall and making good the same.

All materials, labour, T & P etc. shall be arranged by the contractor. The work site shall be cleaned neatly after completion of the work. Material entry in NIB campus will be permitted only with the material challans.

## 2. Eligibility Criteria:

- 2.1 Eligibility will be based on meeting the following minimum criteria regarding the Applicant's work experience, personnel and financial position, as demonstrated by the Applicant's responses in the tender.
- 2.2 The Applicant to meet the following minimum criteria for eligibility:
- (a) Average Annual financial turnover for similar works during the last three financial years, ending 31<sup>st</sup> March, 2017, should be at least **Rs. 5.0 lakh**.
  - (b) Experience of having successfully completed similar works during the last seven years ending 31<sup>st</sup> May, 2018, should be either of the following.
    - a) Three similar completed works each costing not less than the amount equal to **Rs. 0.35 lakh each**.
    - Or
    - b) Two similar completed works each costing not less than the amount equal to **Rs. 0.52 lakh each**.
    - Or
    - c) One similar completed work costing not less than the amount equal to **Rs. 0.70 lakh**.
- 2.3 **Definition of Similar Work: Experience of Civil works including false ceiling work, flooring work such as epoxy flooring/ PVC flooring, Gypsum board partition & glass partition etc. in any Govt. office or large private sector company.**

## 3. Earnest Money Deposit (EMD):

The Bidder shall furnish EMD of **Rs. 1,700/-** (*One thousand seven hundred only*) along with the tender in the shape of demand draft in favour of "**National Institute of Biologicals**" payable at **Noida**. EMD shall be returned to the unsuccessful bidders after award of work. EMD of successful bidder shall be adjusted in the security deposit. The tender not accompanied with EMD shall be rejected. If the bidder fails to accept the order or start the work EMD shall be forfeited.

### For Payment of EMD through Bank transfer:

NAME OF BANK	BANK OF BARODA, SEC-29, NOIDA (U.P)
NAME OF ACCOUNT	NATIONAL INSTITUTE OF BIOLOGICALS
S.B. ACCOUNT	26290100001774
IFSC CODE	BARB0NOIDAX (5 <sup>th</sup> digit is zero)

**In case of EMD deposited through NEFT/ RTGS directly in NIB's Bank Account relevant details should be provided in the Technical-Bid.**

**4. Site Visit:**

a. The bidder is advised to acquaint himself with the work, visit the site & examine site conditions, climatic conditions, labour, power, material availability, transport and communication facilities, environmental regulations, laws and byelaws of statutory, local bodies and the Govt. of India and collect all information that will be necessary for preparing the bid and entering into a contract. The cost of visiting the site and collecting information for the purpose of submission of the bid shall be to the bidder's account.

b. The bidder and any of his personnel or agents will be granted permission by NIB to enter upon the site for the purpose of such inspection.

**5. Submission of Tender:**

The contractor shall submit the tender in the sealed envelope in the following manner.

**Envelope No. 1** - shall contain:

- EMD, in the form of demand draft for **Rs. 1,700/-** (*One thousand seven hundred only*) in favour of **National Institute of Biologicals, Noida.**
- Similar work experience certificates/Work order in support of fulfilling the eligibility criteria.
- Balance sheet of the company for the last three financial years etc.
- A copy of tender document duly signed and stamped by the bidder as a token of acceptance of terms & conditions and Bill of Quantities (BOQ) of the tender (**Page No. 1 to 11**)

**Envelope No. 2** - Shall contain:

- Price-Bid only. Price shall be filled up by the bidder on the Price-Bid format (**Page No. 12-15**) enclosed with the tender by NIB. Price on any other format shall be rejected.

Both the sealed envelopes No. 1 & 2 shall be then put in a bigger envelope duly addressed to "**Director, National Institute of Biologicals, A-32, Sector - 62, Noida-201309**" and marked on top Tender for "**Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms**".

**6. Evaluation & Award of work:**

The bids will be evaluated as per the Eligibility criteria given at Clause -2 above. The bids which are found to be fulfilling the eligibility criteria shall only be considered for opening of Price-Bids. NIB may seek clarifications in the bids from the bidders during the evaluation process. **The Evaluation Committee shall correct arithmetic errors, if any and sign the same. If, any discrepancy is found between the amount in figures and the amount in words, the amount in words shall prevail.**

The work will be awarded to the lowest responsive (L-1), evaluated bidder and Work- order will be issued to the firm. NIB may like to visit the similar completed works of the successful bidder before accepting their bid.

**7. Time of Completion and Extension of Completion Date:**

- i) The work shall be completed within **30 (Thirty) Days** from the date of issue of work order.
- ii) Due to an event, not attributable to the contractor, causing delay, occurs or a variation order is issued, which makes it impossible to complete the work by scheduled completion date, NIB may consider extending the completion date on request of the contractor.

**8. Security Deposit:**

A sum equivalent to 10% of the final value of work shall be deducted from the bill of the contractor, which shall be returned after successful completion of the Defect Liability Period (DLP) of one year.

**9. Liquidated Damages/ Penalty for Delay:**

If the contractor fails to complete the work within the stipulated time or time extended by the Institute (if any), liquidated damages at the rate of 0.5% per week/part thereof delay subject to maximum 10% of the total work value shall be deducted/ recovered from the contractor.

**10. Specifications:**

The materials proposed and supplied for use in the work shall be of requisite specifications as specified in the tender. The works will be carried out as per relevant CPWD specifications and best practices in the Industry.

**11. Defect Liability Period (DLP):**

The materials & work of the contractor shall be under 1 (*one*) *year's Defect Liability Period (DLP)*. Defect/s noticed during the defect liability period shall be rectified by the contractor without any cost to NIB, failing which the Performance Security Deposit of the Contractor shall be forfeited. The contractor may also be debarred from any future tendering in the Institute.

**12. Payment:**

(i) Payment of the contracted price for respective item will be made on receipt of pre-receipted bill & satisfactory completion of work. Final payment will be made within 30 (*Thirty*) days after completion of the work. No advance payment shall be made to start the work. TDS will be deducted as per rules.

(ii) Necessary Bank details need to be provided for release of payment directly in bidder's Bank Account. Bank Details is to filled in the column by bidder as given below:

NAME OF ACCOUNT HOLDER	
NAME OF BANK & ADDRESS	
ACCOUNT NO	
IFSC CODE	
PAN NO	

**13. Bill of Quantity:**

The quantities given in the Bill of Quantities (BOQ) are approximate quantities. There may be 20% increase/decrease in actual work done. The varied quantities of work will be carried out on the tendered rates. Payment shall be made as per the measurement of finished & actual work done at site.

**14. a) Tools & Tackles:**

All tools, tackles such as cutting & drilling machines, ladders, platforms, etc. will be arranged by the contractor and their charges will be deemed to be included in the quoted rates, no extra payment shall be made for the same.

**b) Water & Electricity:**

Water & Electricity will be provided free of cost by NIB, at one point from where contractor will make arrangement of pipes, cables, power plugs, sockets etc. to extend the same to the work place.

**15. Risks:**

Contractor shall be solely responsible for safety of his workers, working at site by taking insurance cover and by following all safety norms in the trade.

All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor. Excepted Risks are:

- a. (i) War, hostilities (whether war be declared or not), invasion, act of foreign enemies.
  - (ii) rebellion, revolution, insurrection, or military or usurped power, or civil war,
  - (iii) Ionising radiations, or contamination by radio-activity from any nuclear fuel, or from any nuclear waste from the combustion of nuclear fuel, radioactive toxic explosive, or other hazardous properties of any explosive nuclear assembly or nuclear component thereof.
  - (iv) Pressure waves caused by aircraft or other aerial devices traveling at sonic or supersonic speed.
- b. Loss or damage due to the use or occupation by the Employer of any section or part of the Permanent Works, except as may be provided for in the Contract.

**16. Disputes:**

If any dispute or difference of any kind, whatsoever, shall arise between NIB and the Contractor, in connection with or arising out of the Contract, or the execution of the works, whether during the progress of the works or after their completion and whether before or after the termination, abandonment or breach of the contract, it shall, be settled under the Indian Arbitration and Conciliation Act, 1996 or any statutory modification or re-enactment thereof and the rules made there under and for the time being in force shall apply to the arbitration proceedings under this clause. Such arbitration shall be settled by Sole arbitrator who shall be appointed by Director, NIB. The arbitration shall take place in Noida/ Delhi unless both parties agree otherwise.

**17. Right to accept or reject the Tender:**

Director, NIB reserves the right to accept or reject any or all the tenders without assigning any reason thereof.

*Stamp of bidder with signature of authorized signatory,*





# NATIONAL INSTITUTE OF BIOLOGICALS

**Plot No.A-32, Sector - 62 (Institutional Area), NOIDA- 201 309 (U.P)**

Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014

E-mail: [info@nib.gov.in](mailto:info@nib.gov.in)

Website: [www.nib.gov.in](http://www.nib.gov.in)

## BILL OF QUANTITY (BOQ)

**Tender No. 07/2018-2019/Engg. (C)**

**Name of Work:** Tender for “Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms”.

<i>Srl No</i>	<i>Description of items</i>	<i>Unit</i>	<i>Qty.</i>
1.	Providing and laying CPVC pipe including all fittings, over/under the gypsum board/partition/false ceiling including clamping and making the hole/cut made for passing water line.		
	20 mm Nominal outer dia pipe.	Rmt.	10
2.	Providing & fixing gun metal Gate Valve with C.I wheel of approved quality (Screwed end)		
	20 mm nominal dia	Each	01
3.	Providing and fixing anti-Siphon PP Bottle Trap for Sink Complete Work. 40mm dia	No.	01
4.	Providing and fixing bench mounted 1 way water fitting with 8”rigid/swing Gooseneck for Raw water/R.O Water.	No.	01
5.	Providing and fixing Stainless Steel, Sink of size: 560(L) x 355(D)x 245 (H) and Bowl size: 500(L) x 293(D)x 245 (H) in SS 304 grade with waste jali etc.	No.	01
6.	Cutting holes up to 15x15 cm in gypsum partition wall for passing drain pipe etc. and repairing & making good same after laying pipe etc. Complete Work.	Each	03
7.	Making chases up to 7.5x7.5 cm in walls/floor including making good and finishing with matching surface after housing drain pipe etc.	Rmt.	06
8.	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes SDR 7.4, U V Stabilized & anti-microbial fusion welded, having thermal stability for hot & cold water supply, including all PP-R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes testing of joints complete as per direction of Engineer in Charge.		
	PN-16 Pipe, 50 mm OD.	Rmt.	06
9.	Making water connection from SS pipe mains including providing fittings such as SS Socket, nipple, Male/Female Tee etc. Complete Work.	L-S	01
10.	Providing & fixing 12 mm thick toughened Glass water spill barrier of approx. 3’x 1.5’ size on the existing counter, including sealing the gap with Silicon Sealant. Complete Work.	Sqm.	01

11.	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete.		
	75mm overall thickness partition with 12.5 mm thick double skin tapered edged plain Gypsum board conforming to IS:2095: part I	Sqm.	6.5
12.	Painting on wall/false ceiling/ gypsum board partition, with epoxy paint two or more coats on new/old work with approved quality epoxy paint of ICI Dulux or equivalent make.Two or more coats to make the surface smooth. Complete Work.	Sqm.	6.5
13.	Providing & fixing PVC Flase Ceiling of M/s Plasopan/equivalent make, as per the following specifications: (i) Frame will be made of electric resistant welded semi-bright steel tube of size 25mmx25mm. (ii) The grid size of the frame will be not more than 600mmx 1100mm. (iii) A Upvc hollow section of size 250mmx10mmx1mm ± 0.3mm average wall thickness will be fixed to the frame in such a way to conceal the tubular frame, with the help of self tapping steel screws placed at interval of 600mm.	Sqm.	19.00
14.	Providing & laying 3 mm thick Epoxy Flooring as per approved colour shade. Complete work as per direction of NIB.	Sqm.	22
15.	Providing & making Epoxy Coving as per approved colour shade between wall and floor. Complete work as per direction of NIB.	Rmt.	30
16.	Extra for providing opening of required size & shape for wash basin/kitchen sink in kitchen platform, vanity counter and similar	Each	01

	location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.		
17.	Disposal of building rubbish/malba/ similar unserviceable, dismantled or waste material by mechanical means, including loading, transporting, unloading to approved municipal dumping grounds beyond 50m initial lead, for all leads including all lifts involved.	Cum	02
	<b><u>OPTIONAL ITEM:</u></b>		
18.	Removing old mild steel doors with frames from gypsum partitions and reinstallation in gypsum partition in proper alignment with all fittings and fixtures as per old fixing arrangement i.e. by using hard wood battens, G.I. Channels, nuts, bolts etc. including making good the peripheral area of the door after reinstallation.	01 Nos.	Rate only
	<b><u>Total</u></b>		

*Stamp of bidder with signature of authorized signatory,*



**NATIONAL INSTITUTE OF BIOLOGICALS**  
**Plot No. A-32, Sector - 62 (Institutional Area), NOIDA- 201 309 (U.**  
Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014  
E-mail: [info@nib.gov.in](mailto:info@nib.gov.in) Website: [www.nib.gov.in](http://www.nib.gov.in)

**PRICE-BID**

**Tender No. 07/2018-2019/Engg. (C)**

**Name of Work:** Tender for "Shifting of Sterility Lab. in NIB Noida, Sh: Providing & fixing PVC False Ceiling in Room No. S0130A, Epoxy Flooring and petty civil works at ground floor, Lab. Rooms".

<i>Srl No</i>	<i>Description of items</i>	<i>Unit</i>	<i>Qty.</i>	<i>Rate (Rs.)</i>	<i>Amount (Rs.)</i>
1.	Providing and laying CPVC pipe including all fittings, over/under the gypsum board/partition/flase ceiling including clamping and making the hole/cut made for passing water line.				
2.	20 mm Nominal outer dia pipe.	Rmt.	10		
	Providing & fixing gun metal Gate Valve with C.I wheel of approved quality (Screwed end)				
3.	20 mm nominal dia	Each	01		
	Providing and fixing anti-Siphon PP Bottle Trap for Sink Complete Work. 40mm dia	No.	01		
4.	Providing and fixing bench mounted 1 way water fitting with 8"rigid/swing Gooseneck for Raw water/R.O Water.	No.	01		
5.	Providing and fixing Stainless Steel, Sink of size: 560(L) x 355(D)x 245 (H) and Bowl size: 500(L) x 293(D)x 245 (H) in SS 304 grade with waste jali etc.	No.	01		
6.	Cutting holes up to 15x15 cm in gypsum partition wall for passing drain pipe etc. and repairing & making good same after laying pipe etc. Complete Work.	Each	03		
7.	Making chases up to 7.5x7.5 cm in walls/floor including making good and finishing with matching surface after housing drain pipe etc.	Rmt.	06		
8.	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes SDR 7.4, U V Stabilized & anti-microbial fusion welded, having thermal stability for hot & cold water supply, including all PP-R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes testing of joints complete as per direction of Engineer in Charge.				

9.	PN-16 Pipe, 50 mm OD.	Rmt.	06		
	Making water connection from SS pipe mains including providing fittings such as SS Socket, nipple, Male/Female Tee etc. Complete Work.	L-S	01		
10.	Providing & fixing 12 mm thick toughened Glass water spill barrier of approx. 3'x 1.5' size on the existing counter, including sealing the gap with Silicon Sealant. Complete Work.	Sqm.	01		
11.	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm diameter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete.				
	75mm overall thickness partition with 12.5 mm thick double skin tapered edged plain Gypsum board conforming to IS:2095: part I	Sqm.	6.5		

12.	Painting on wall/false ceiling/gypsum board partition, with epoxy paint two or more coats on new/old work with approved quality epoxy paint of ICI Dulex or equivalent make. Two or more coats to make the surface smooth. Complete Work.	Sqm.	6.5		
13.	Providing & fixing PVC False Ceiling of M/s Plasopan/equivalent make, as per the following specifications: (iv) Frame will be made of electric resistant welded semi-bright steel tube of size 25mmx25mm. (v) The grid size of the frame will be not more than 600mmx 1100mm. (vi) A Upvc hollow section of size 250mmx10mmx1mm ± 0.3mm average wall thickness will be fixed to the frame in such a way to conceal the tubular frame, with the help of self tapping steel screws placed at interval of 600mm.	Sqm.	19.0 0		
14.	Providing & laying 3 mm thick Epoxy Flooring as per approved colour shade. Complete work as per direction of NIB.	Sqm.	22		
15.	Providing & making Epoxy Coving as per approved colour shade between wall and floor. Complete work as per direction of NIB.	Rmt.	30		
16.	Extra for providing opening of required size & shape for wash basin/kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	01		
17.	Disposal of building rubbish/malba/ similar unserviceable, dismantled or waste material by mechanical means, including loading, transporting, unloading to approved municipal dumping grounds beyond 50m initial lead, for all leads including all lifts involved.	Cum	02		
	<b><u>OPTIONAL ITEM</u></b>				
18.	Removing old mild steel doors with frames from gypsum partitions and reinstallation in gypsum partition in proper alignment with all fittings and fixtures as per old fixing arrangement i.e. by using hard wood battens, G.I. Channels, nuts, bolts etc. including making good the peripheral area of the door after reinstallation.	No.	01		
	<b><u>Total</u></b>				

	Goods & Services Tax {GST} (as applicable)				
	<u>Total amount with Taxes</u>				

**Amount(inwords):**

.....  
.....

**Note:**

- i) *Validity of Bid shall be 90 days from the last date of submission of the bid.*
- ii) *Taxes % and amount, if, not specified in Price-Bid will be treated as inclusive and basic rates will be arrived after reverse calculation of GST as applicable.*
- iii) *Any vague term such as GST as per Rule as applicable will not be considered for evaluation.*

*Stamp of bidder with signature of authorized signatory*