

**TENDER DOCUMENT**  
**FOR**  
**RENOVATION OF GUEST HOUSE IN NIB CAMPUS NOIDA**  
**VOLUME -V**  
**BILL OF QUANTITY (BOQ)/ PRICE BID**  
**Tender No: 02/NIB/2017-2018/ Engg. (C/E)**

**APRIL - 2017**



**NATIONAL INSTITUTE OF BIOLOGICALS**  
(Ministry of Health & Family Welfare)  
Plot No. A-32, SECTOR- 62 (Near NH-24),  
NOIDA - 201 309 (U.P)

Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014

e-mail: [info@nib.gov.in](mailto:info@nib.gov.in)

Website: [www.nib.gov.in](http://www.nib.gov.in)

**PREAMBLE TO BILL OF QUANTITIES/ PRICE-BID**

*(These preambles apply to all the sections of the Bill of Quantities. The Contract rates shall take into account all these provisions in addition to various provisions in other parts of the Contract document)*

<b>Srl. No.</b>	<b>Description</b>
1.	This is an "item Rate Tender". Rates shall include cost of material, labour, taxes, duties (including service tax) and all necessary apparent services required for complete execution and commissioning in accordance with relevant specifications. NIB decision on interpretation of bill of quantities and its preamble shall be final and binding on the contractor.
2.	The quantities given in this Bill of Quantities are liable to variations. Such variations in quantities shall not, however, vitiate the contract in any way whatsoever and all quoted rates shall remain valid as per deviation limits provided in the contract. Contractor shall be paid for the actual measured quantities of work executed by him/ them.
3.	Rates quoted shall be firm and shall not be subject to any price variations except as specifically provided in the contract.
4.	The contractor's quoted rate shall include surveying, making layout and demarcation of all services as required for completion of the works within the scope of this contract.
5.	The works "as specified", "as described", "as shown", "as directed", or "as approved", shall mean as described in the specifications, schedule of Quantities and other Contract documents or as directed by NIB.
6.	The following notations as appearing in the Bill of Quantities and Specification shall mean:
	a) CUM/ Cum = Cubic Metre
	b) Sqm. = Square Metre
	c) Rm/ Mtr/ Metre = Running Metre
	d) No. /Nos./ Each/ Set = Numbers
	e) Kg. = Kilogram
	f) Mt. = Metric Ton
7.	The bidders shall take into account all leads and lifts involved in transport of materials to site, erection and hire of T & P,, sheds for materials etc. while quoting the rates for various sub heads of the work. Similarly all taxes including Octroi, Toll or Sales Tax/ VAT, Works Contract tax etc. as payable by the contractor at the time of submission of bids shall be taken into account by the bidders before quoting their rates. Service tax shall be paid extra. Any claim in these matters whatsoever in this respect shall not be entertained.



**NATIONAL INSTITUTE OF BIOLOGICALS**  
**Plot No.A-32, Sector-62(Near NH-24), NOIDA-201 309 (U.P)**  
Tel: 0120-2400022, 2400072, Fax: 0120-2400074, 2403014  
E-mail: [info@nib.gov.in](mailto:info@nib.gov.in) Website: [www.nib.gov.in](http://www.nib.gov.in)

---

**PRICE - BID**

**Summary of Price**

**Name of Work:** Renovation of Guest House in NIB Campus Noida.

<b>Srl. No.</b>	<b>Description</b>	<b>Amount</b> <i>(in figure &amp; words)</i> <b>(Rs.)</b>
<b>A-</b>	<b>Civil Works</b>	
<b>B-</b>	<b>Electrical Works</b>	
	<b>Total (A+B)</b>	

**BILL OF QUANTITIES/ PRICE-BID****Name of Work: Renovation of Guest House in NIB Campus Noida.**

<b>Srl. No.</b>	<b>Description of Items</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (in figure &amp; words) (Rs.)</b>	<b>Amount (in figure &amp; words) (Rs.)</b>
<b>A-</b>	<b><u>Civil Works:</u></b>				
	<b><u>Dismantling &amp; Demolishing:</u></b>				
1.	Dismantling tile work in floor and roof laid in cement mortar including stacking material within 50 meters lead Wall Tiles, 5mm thick 8"x4" size.	Sqm.	456		
2.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal or rubbish to the dumping ground within 50 meters lead.	Sqm.	456		
3.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 meters lead (Old Udaipur green stone).	Sqm.	135		
4.	Demolishing RCC work manually/ by mechanical means including stacking of steel bras and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge (Roof Slab cutting).	Cum.	0.49		
5.	Demolishing brick work manually/ by mechanical means including stacking serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge.	Cum.	4.05		

6.	i) Taking out existing wooden door shutter, repair by cutting, painting etc. and re-fixing of repaired door shutters to existing door frames, including replacement of hinges with screws etc. as required, all complete as per the direction of the Engineer-in-charge.	Each	58		
	ii) Modifying existing aluminum door of size 3'x7' removing floor spring, filling the depression with cement mortar and fixing aluminum hinges, including providing new section for making one side opening.	Each	08		
7.	Removing aluminum glazed door of size 5'x9' approx. and stacking at site.	Job Work	01		
8.	Dismantling conlead pipes from wall/floors 15 to 40mm dia (22 Wash Rooms internal pipes).	Job Work	22		
9	Removing all old & new fittings & fixtures and stacking as per direction: (i)Wash Basins (ii) WC (iii) Wall Mixer (iv) Wash Basin Mixer (v) Angle Valves (vi) Bib Cock (vii) Towel Rack (viii) Towel Rod (ix) Shower Head (x) Flush Valve (xi) Tissue Paper Holder (xii) Soap Dish (xiii) Floor Jali etc. all complete, (22 Washes Room).	Job Work	22		
10.	Dismantling 15 to 40 mm dia G.I. pipe including stacking of dismantled pipes within 50 meters lead as per direction of Engineer-in-charge. (a) Internal work - Exposed on wall.	Meter	224		
	<b><u>Total</u></b>				
	<b><u>Flooring &amp; Tiling:</u></b>				
11.	Providing & fixing 18mm thick gang saw cut, mirror polished, premoulded and pre-polished, machine cut for kitchen plate forms, vanity counters, window sills, facias and similar location of required size, approved shade, colour and texture laid over 20mm thick base cement mortar 1:4: (1 cement: 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Area of slab over 0.50 Sqm.	Sqm.	17.50		

12.	Providing edge moulding to 18mm thick marble stone counters, Vanities etc. including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-charge. Granite work.	Mtr.	65		
13.	Extra for providing opening of required size & shape for Wash Basin/ Kitchen Sink in Kitchen Plateform, Vanity counter and similar locations in marble/Granite/stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	20		
14.	Providing & fixing four sided V Groove Laminate flooring in the double inter locking system of thickness 14 mm with a sound proof packing 2mm thick which reduces the sound up to 50%. Approx. Size: Panels 1215 x 143 x(12+2mm).	Sqm.	602		
15.	Providing and fixing end profile T shaped, made up of Laminate, at the start and end of Laminate flooring jointed with the existing flooring, using standard adhesive as per manufacturer's direction.	R.mtr.	55		
16.	Providing and installation of laminate skirting of 12mm thick and 100mm high as per instructions from NIB, applying standard recommended adhesive/ tape to hide joints.	R.mtr.	450		
17.	Providing and laying rectified Glazed Ceramic floor tiles of size 300mmx300mm or more (thickness to be specified by the manufacture), of 1 <sup>st</sup> quality confirm to IS: 15622, or approved make, in all colours, shades except White, Ivory, Grey, Fume Red Brown, laid on 20mm thick Cement Mortar 1:4 (1Cement :4Coarse sand), jointing with grey cement slurry@ 3.3kg/sqm. including pointing the joints with white cement and matching pigments etc. complete.	Sqm.	100		
18.	Providing & fixing 1 <sup>st</sup> quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-charge, in skirting, risers of steps and dados, over 12mm thick bed of cement mortar 1:3 (1 Cement:3 Coarse sand)	Sqm.	460		

	and jointing with grey cement slurry @ 3.3 kg per sqm. Including pointing in white cement mixed with pigment of matching shade complete. Size more than 300x300mm, Basic Rate of tiles to be minimum Rs. 400/- Sqm.				
19.	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% any conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6mm thickness, including grouting of joints. Size of tile 600x600mm.	Sqm.	294		
20.	Providing & laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6mm thickness, including grouting of joints. Size of tile 600x600 mm	Sqm.	24		
	<b>Total</b>				
	<b>Reinforced Cement Concrete:</b>				
21.	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20mm nominal size).	Cum.	0.49		
22.	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.	Per 50 Kg. Cement Bag	04		
	<b>Total</b>				

<b>Brick Work &amp; Plaster:</b>					
23.	Brick work with common burnt clay FPS (non-modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in: Cement mortar 1:6 (1 cement: 6 coarse sand).	Cum	01		
24.	i) 12mm Cement plaster of mix. 1:6 (1 cement: 6 coarse sand).	Sqm.	05		
	ii) 15mm cement plaster on rough side of single or half brick wall of mix. 1:6 (1 cement: 6 coarse sand).	Sqm.	05		
25.	Half Brick masonry with common burnt clay FPS (non-modular) bricks of class designation 7.5 in superstructure plinth level up to floor V level. Cement Mortar 1:4 (1cement: 4 coarse sand).	Sqm.	27.50		
26.	Repair of plaster of thickness 12mm to 20mm in patches of area 2.5sq. meters and under, including cutting the patch in proper shade raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground all complete as per directions of Engineer-in-charge. With cement mortar 1:4 (1 cement: 4 coarse sand).	Sqm.	27.50		
27.	Washed stone grit plaster on exterior walls height up to 10 meter above ground level, in two layer, 12mm cement plaster 1:4 (1 cement: 4 coarse sand), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2kg of cement per square metre, top layer 15mm cement plaster 1:1/ 2:2 (1 cement: ½ coarse sand: 2 stone chipping 10mm nominal size), in panels with groove all around as per approval pattern, including scrubbing and washing the top layer with brushes and water top expose the stone chippings, complete as per specification and direction of Engineer-in-charge (payment for providing grooves shall be made separately).	Sqm.	18.5		



28.	Extra for using white cement in place of ordinary cement in the top of the item of washed stone grit plaster.	Sqm.	18.5		
29.	Forming groove of uniform size in the top layer of washed stone grit plaster as per approved pattern using wooden battens, nailed to the under layer, including removal of wooden battens, repair to the edges of panels and finishing the groove complete as per specifications and direction of the Engineer-in-charge. 20mm wide and 15mm deep groove.	Metre	58		
	<b>Total</b>				
	<b>Pipes &amp; Fittings:</b>				
30.	Providing & fixing Chlorinated Polyvinyl Chloride (CPVC), pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer-in-charge. 20mm nominal outer dia Pipes	Meter	346		
31.	Providing & fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fitting, including fixing the pipe with clamps at 1.00m, spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer-in-charge.				
	i) 40mm nominal outer dia Pipes.	Meter	121		
	ii) 50mm nominal outer dia Pipes.	Meter	98		
32.	Providing & fixing gun metal gate valve with C.I. wheel of approved quality (Screwed end).				
	i) 25mm nominal bore.	Each	02		
	ii) 40mm nominal bore	Each	09		

	iii)50mm nominal bore	Each	09		
33.	Making connection of G.I. distribution brach with G.I. main of following sizes by providing and fixing tee, including cutting ad threading the pipe etc. complete.				
	i) 25 to 40 mm nominal bore.	Each	09		
	ii) 50 to 80 mm nominal bore	Each	09		
34.	Providing & fixing GI pipes complete with GI fittings and clamps, i/c cutting and making good the walls etc.				
	i)25mm dia nominal bore.	Meter	07		
	ii)32mm dia nominal bore.	Meter	28		
35.	Providing & fixing GI Union in GI pipe including cutting and threading the pipe and making long screws etc. complete (New Work).				
	i)25mm nominal bore.	Each	02		
	ii)32mm nominal bore.	Each	02		
	<b>Total</b>				
	<b><u>Wash Room Fittings:</u></b> <b>for Jaquar make fittings &amp; fixtures refer Catalouge No. Volume 13A/October, 2016.</b>				
36.	i) Providing & fixing overhead Showers 150x150 Square shape single flow (ABS Body Chorme Plated with Gray Face Plate) with rubit cleaning System. Jaquar make (Model No. OHS-35495) or equivalent complete as per direction of NIB.	Each	22		
	ii) Providing & Fixing CP brass Shower Arm Casted 190mm long light body round shape for wall mounted showers with flange of Jaquar make, (Model No. SHA 477) or equivalent complete as per direction of NIB.	Each	22		
37.	Providing & fixing Corner Glass Shelf (with bracket) Jaquar make, (Model No. ACN-1173) or equivalent complete as per direction of NIB.	Each	22		

38.	Providing & fixing Single lever Sink Mixers Swinging Spout (wall mounted model) with connecting legs & wall Finges. Jaquar make, (Model No. SOL-6163) or equivalent complete as per direction of NIB.	Each	10		
39.	Providing & fixing Under Counter Wash Basin, Size: 550x425x195 mm in white colour. (Model No. FLS-WHT-5701) or equivalent complete as per direction of NIB.	Each	20		
40.	Providing & fixing CP Central Hole Basin, Mixer without Popup. Waste system with 450mm long Braided Hoses. (Model No. CON-167KNB) or equivalent complete as per direction of NIB.	Each	20		
41.	Providing & fixing CP Angle Valve (for Wash Basin & Geyser)/Angular Stop Cock. (Model No. CON-053KN) or equivalent complete as per direction of NIB.	Each	80		
42.	Providing & fixing CP concealed stop cock, Regular Body with adjustable wall flange size 15mm Jaquar make, (Model No. CON-069KN) or equivalent complete as per direction of NIB.	Each	40		
43.	Providing & fixing CP 2-Way Bib-Cock Jaquar make, (Model No. CON-041KN) or equivalent complete as per direction of NIB.	Each	20		
44.	Providing & fixing CP Wall Mixer with Hand Shower arrangement with connecting legs, wall flanges, and wall bracket for Hand shower, Jaquar make, (Model No. CON-267KN) or equivalent complete as per direction of NIB.	Each	20		
45.	Providing & fixing Hand shower $\Phi$ 140mm round shape, Single Flow with Air Effect (ABS Body & face plate chrome plated) with Rubit cleaning systems, Jaquar make, (Model No. HSH-1727) or equivalent complete as per direction of NIB.	Each	20		
46.	Providing & fixing Easy flexible tube 8mm in chrome finish minimum 1.5m long with nuts, Jaquar make, (Model No. SHA-571) or equivalent complete as per direction of NIB.	Each	20		
47.	Providing & fixing Premium Wall Bracket for Hand shower $\Phi$ 35mm and 100mm long round shape with Nuts, Jaquar make, (Model No. SHA-555) or equivalent complete as per direction of	Each	20		

	NIB.				
48.	Providing & fixing Waste coupling 32mm size full thread with 80mm height, Jaquar make, (Model No. ALD-705) or equivalent complete as per direction of NIB.	Each	20		
49.	Providing & fixing CP Bottle trap (with internal partition) 32 mm size with 250 mm & 190mm long wall connection pipes & wall flange, Jaquar make, (Model No. ALD-769L300X190) or equivalent complete as per direction of NIB.	Each	30		
50.	Providing & fixing Hand Shower (Health faucet) (ABS Body) with 1 (ABS Body) with 1Meter long easy flex tube in Chrome finish with wall Hook complete, Jaquar make, (Model No. ALD-CHR-585) or equivalent complete as per direction of NIB.	Each	20		
51.	Providing & fixing Toilet Roll Holder with Flap, Jaquar make, (Model No. ACN-1153N) or equivalent complete as per direction of NIB.	Each	20		
52.	Providing & fixing Single Towel Rail 450mm long, Jaquar make, (Model No. ACN-1111-BNM) or equivalent complete as per direction of NIB.	Each	20		
53.	Providing & fixing Towel Rack with lower Hanger Stainless Steel (SS) with Hook minimum 600 mm long, Jaquar make, (Model No. AHS-1581H) or equivalent complete as per direction of NIB.	Each	20		
54.	Providing & fixing Soap Dish Holder Jaquar make, (Model No. AKP-35731P) or equivalent complete as per direction of NIB.	Each	20		
55.	Providing & fixing 5mm beveled edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with CP brass screws and washers complete.				
	i) Size 1500x900 approx.	Each	08		
	ii) Size 0.900x0.900 approx	Each	12		
56.	Providing & fixing Flush Valve complete with 32mm size Control Cock with Elbow Set & Wall Flanges (Regular Size), Jaquar make, (Model No. FLV-1015) or equivalent complete as	Each	20		

	per direction of NIB.				
57.	Providing & fixing Wall Hung WC Pan Model No CD2006P23/05, Make: Hindware Ultra in white colour.	Each	20		
58.	Providing & fixing Cast Iron Brackets suitable for fixing WC Pan complete as per direction of NIB. Hindware make, for Model No. CD2006P23/05.	Pair	20		
59.	Providing & fixing Seat Cover for WC Pan for Model No. E8094 Hindware make	Each	20		
60.	Providing & fixing CP floor Jali $\Phi$ 100 mm complete as approved.	Each	40		
61.	Providing & fixing PVC Connections complete as approved.	Each	80		
62.	Providing & fixing 12mm thick Toughned glass partition in Wash Room including providing SS Rod & brackets for supporting the partition from wall to wall complete work. Make: Modi float/ Saint Gobain/ Asai.	Sqm.	58.50		
63.	Providing & fixing cast iron brackets for fixing Wash Basin in granite slab including (Wash Basin model No. FLS-WHT-5701) carbon steel dash fastners complete work.	Pair	20		
64.	Shifting of floor traps by 10Cm to 15Cm from its existing location including supply of all materials etc. complete.	Job.	20		
	<b><u>Total</u></b>				
	<b><u>Painting &amp; Polishing:</u></b>				
65.	Removing dry or Oil bound distemper, water proofing cement paint and the like scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm.	3500		
66.	Providing and applying plaster of Paris putty of 2mm thickness over plastered surface t prepare the surface even and smooth complete.	Sqm.	10		
67.	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade. One or more coats on old work.	Sqm.	3500		

68.	i) French sprit polishing. One or more coats on old wood work.	Sqm.	273		
	ii) French sprit polishing in wooden hand rail size 2"x2" and 2½" x 2¾" approx.	Meter	60		
69.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work.	Sqm.	60		
	<b>Total</b>				
	<b>Site Cleaning:</b>				
70.	Disposal of building rubbish/malba/similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineering-in-charge, beyond 50m initial lead, for all leads including all lifts involved.	Cum	13		
	<b>Total</b>				
	<b>Sub Total (A)</b>				
<b>B-</b>	<b>Electrical Works:</b>				
1.	Cutting/ chasing of wall and floor to a maximum width and depth of 75mm by manual/ mechanical means, for laying conduits/ raceways etc. and subsequent repair to give neat levelled surface using by laying PCC of same grade of existing contract etc. all complete.	Rmtr.	175		
2.	Providing and installation of 25mm diameter fire proof PVC conduits, bends, T's etc. (Setia/ AKG make) concealed in walls and ceiling. The above shall also include chasing of wall placing and fixing of conduits with suitable brackets/ supports and subsequent repair in plaster to give a neat finish all complete. This shall also include the repair work/ making good any damage/ breakage done to the walls/ ceiling or any other route, to be finished in the existing specifications so as to give a complete and neat look.	Rmtr.	175		

3.	Providing and fixing of MS Box of required sizes. This shall also include the repair work/ making good any damage/ breakage done to the walls/ ceiling or any other route, to be finished in the existing specifications so as to give a complete and neat look.	Nos.	154		
4.	Providing and installation of multi strand copper Wiring of required cores (Anchor make) in marked area (concealed in wall using conduits 25 mm diameter or higher dia. as required). Following cores of wires to be provide-				
	i) 2.5 Sq.mm. core (L&N)	Rmtr.	175		
	ii) 1.5 Sq. mm. (E)	Rmtr.	770		
5.	Providing and installation of Cat-6 wire confirming to ITD-S/SW-113B in 20mm dia 16SWG (Delton, Delink make) in marked area (concealed in wall using conduits 25 mm diameter or higher dia. as required).	Rmtr.	150		
6.	Providing and installation of Telephone wire 4-pair (Delton, Satia Delink make) in marked area (concealed in wall using conduits 25 mm diameter or higher dia. as required).	Rmtr.	150		
7.	Providing and installation at positions modular switches, sockets of (North West/ Anchor Roma make) including switch box cover plate, chasing of walls and subsequent repair of wall for installation of switch boards for following quantity (note-in case of modular work stations, long wires shall be left to embed in provided raceway of work station later on and switches and sockets as per drawing to be fixed after supply of work stations) --				
	(i) 6 Amp Switch in Switch Boards.	Nos.	266		
	ii) 6A switch and Sockets	Nos.	154		
	iii) 16 Switch and Sockets	Nos.	98		

	v) Telephone Outlet Point	Nos.	28		
	vi) Fan Regulator	Nos.	56		
	vii) LAN Outlet Point -RJ-45	Nos.	28		
8.	Providing and installation of LED wall light metal and sinthic (140x140x37mm) adjustable neck to direct litht fixtures Phillips/ CG/Havels/Jaquar make including choke etc. all complete. as per the new light all complete.	each	40		
9.	Providing & fixing of Exhaust fan 9"x12" to Havels/ CG make all complete.	each	20		
10.	LED Bulb 14W, Philips	Nos.	84		
11.	LED Light fixture, 4' 18W, Philips	Nos.	28		
12.	LED Light fixture, 2' 18W, Philips	Nos.	44		
13.	LED Panel 15W Surface, Philips	Nos.	91		
14.	Double wall light Glass colourful handmade metal-Alloy.	Nos.	84		
15.	Providing & fixing of Door Bell point including Bell Phillips/ Havels/ CG make all complete.	Nos.	20		
16.	Providing & fixing of LED (7W to 10W) down light 124mm White & Aluminium santhic Phillips/ Havels/ CG make all complete.	Nos.	85		
17.	Providing & fixing of 20w surface panel White & Aluminium santhic Phillips/ Havels/ CG make all complete.	Nos.	05		



18.	Providing & fixing of 20w to 36w LED light fixture Wall mounted White & Aluminium santhic Phillips/ Havels/ CG make all complete.	Nos.	01		
	<b><u>Total (B)</u></b>				
	<b><u>Total (A+B)</u></b>				
	Service tax etc. @..... if any				
	<i>Total amount with tax</i>				

**Amount (in words):** .....

.....

**Note:**

- i) *Validity of Bid shall be 90 days from the last date of submission of the bid.*
- ii) *Taxes/ duties not specified in Price-Bid will be treated as inclusive.*
- iii) *The bidders are strongly advised to go through the complete bid document, visit the site and participate in the Pre-Bid meeting to understand the scope of work before quoting their rates.*

*Stamp of bidder with signature of authorized signatory,*